



		, [
House Type 1		
Family Size:	9/10 maximum	
Gross Area:	721sqft / 67m2	
Gross Internal Area:	502sqft / 46m2	
House Type 2		
Family Size:	7 maximum	
Gross Area:	641sqft / 60m2	

Project Type

- Housing reconstruction in earthquake affected areas
- Recipients are the most vulnerable in the community who cannot self-build
- Incorporating seismic resistance measures
- Delivering training workshops to local community members
- Budget of approximately Rs290 000 per house

Project Partner

Muslim Aid UK / Muslim Aid Pakistan

Context

- Pakistan Earthquake, October 8th 2005: 7.6 on the Richter Scale
- Deaths estimated at between 70,000 and 80,000, similar number injured
- Upwards of 3 million people made homeless

Project Location

- Bagh, Azad Jammu & Kashmir and Jareed, North West Frontier Province
- Rural, mountainous terrain

No. Houses Constructed

• 60 - 80 by September 2008 when project is programmed to complete

Shelter Type


- Dhajji Da (patchwork of timber and stone) houses on stone plinth
- Mud, stone and straw infill with mud render finish •
- Lightweight timber structure with corrugated metal sheet roof •
- Dhajji Da is a construction type indigenous to the region •
- Small bracing members spread seismic energy, reduce risk of damage •
- a[25] design approved by regulatory authorities: NESPAK, ERRA





















Detail Design

- a[25] consultancy service includes comprehensive detail design •
- Robust detailing ensures high quality construction
- Appropriate detailing ensures value for money •
- Details developed by a[25]'s experienced built environment specialists Local and international consultants provide input where required
- Various methods used to explain detail design e.g. models, sketches
- Details refined for maximum buildability and cost efficiency

Detail Drawings


- Developed as part of a coordinated package of production information
- a[25] produced additional drawings during the works to help explain key structural details to construction workers

Timber Joint Samples


- Constructed by local carpenters in cooperation with UN-HABITAT
- Samples demonstrated key structural details
- a[25] used samples onsite as training aids for carpenters
- Effective communication of required workmanship to labour
- Enabled rapid improvement of the skills in the community


Visual Construction Guidelines

- Hand-drawn diagrams explaining construction process
- Complex construction methods described step by step in simple format
- Used as a training aid for non-technically skilled community members









Production Information


Two house designs developed following research into the following:

- Seismic mitigation measures •
- Vernacular construction methods •
- Family size and domestic requirements particular to the area •
- Materials and skills available locally •
- Logistical challenges e.g. transportation of materials to site •
- Most cost effective construction technique •

Drawing Package

- a[25] produced full package of drawings for each house type •
- Information comprised plans, sections, elevations and details •
- Drawings submitted to NESPAK (National Engineering Services Pakistan • Ltd) and ERRA (Earthquake Reconstruction & Rehabilitation Authority) for approval
- Both house designs received official approval for construction in less than • three months

Top Left	- House Type 2 - Ground Flo
Bottom Left	- House Type 2 - Front Elev
Bottom Right	- House Type 2 - Section A:



loor Plan ation / Timber Frame & Infill :A









Construction Management

- a[25] project manager present to regularly monitor work on site
- Onsite supervision mitigates risk of costly construction errors
- a[25] project manager coordinates with local partner organisations •
- Construction undertaken by local contractors and local labour
- The local economy benefits from the construction •

Construction Process

Each house requires approximately 100 working days to complete

Plinth Construction: Primary construction phases

- **1.** Site selection 2. Demarcation
- **3.** Excavation
- **5.** Masonry plinth wall

Frame Construction: Primary construction phases

- **2.** Fix metal roof sheet **1.** Construct frame
- **3.** Construct bracing
- **5.** Electrics / plumbing work

Seismic resistance measures:

- Seismic bands tie the structure together
- Multiple small bracing members spread seismic energy
- Timber joints used approved by ERRA and NESPAK
- Galvanised steel straps add strength at joints between timber members
- Foundation and plinth bands reinforced to NESPAK approved standard •





- **4.** Pour reinforced concrete foundation 6. Pour reinforced concrete plinth band
- 4. Stone, mud, infill / mud, straw floor **6.** Finishing work



